BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of Work: **Construction of Gazibo at Suverna Mahothsava Ground (NTI Ground) at Vidyaranyapura Main Road in Ward No. 09, Vidyaranyapura Sub Division.**

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates KRIDL		
				In Figures	Amount	In Words
1	60.00	Earth work in surface excavation in **ordinary soil** for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	156.88	9412.80	Rupees One Hundred Fifty Six and Eighty Eight Paise Only
2	48.00	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in Ordinry soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	188.68	9056.64	Rupees One Hundred Eighty Eight and Sixty Eight Paise Only
3	19.89	Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	4976.70	98986.56	Rupees Four Thousand Nine Hundred Seventy Six and Seventy Paise Only
4	18.00	Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6**, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	4058.74	73057.32	Rupees Four Thousand Fifty Eight and Seventy Four Paise Only
5	10.44	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	4814.52	50263.59	Rupees Four Thousand Eight Hundred Fourteen and Fifty Two Paise Only
6	48.00	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	127.20	6105.60	Rupees One Hundred Twenty Seven and Twenty Paise Only
7	31.20	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	97.52	3042.62	Rupees Ninety Seven and Fifty Two Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-Division
KRIDL, BBMP, Bangalore

11/7/16

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates KRIDL		
				In Figures	Amount	In Words
8	10.22	Providing and laying in position **reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal**, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	6083.34	62171.73	Rupees Six Thousand Eighty Three and Thirty Four Paise Only
9	1.02	KSRB 4.9.2: Providing **T.M.T steel reinforcement for R.C.C** work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars Fe 500 etc., complete and as per the directions of the Engineer-in-charge of the work	Tonne	61722.99	62957.45	Rupees Sixty One Thousand Seven Hundred Twenty Two and Ninety Nine Paise Only
10	8.64	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface such as walls at any thickness**, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	301.04	2600.99	Rupees Three Hundred One and Four Paise Only
11	253.44	Providing andfixing of pre pigmneted extruded orange cement roof tiles of zixe 420 mmx 330 mm with necessary pecials such as ridges barges and nils etc. including cast of providing PVC (6.00 kgs/sqcm) gutter of min 6" radius and down water pipes of 4" dia as per the roof design on EXISTING MS/WOODEN ROOF OR TRUSS INCLUDING cost of materials, scaffoldings, labour etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	755.78	191544.88	Rupees Seven Hundred Fifty Five and Seventy Eight Paise Only
12	5153.57	Fabricating Supplying and erecting M.S. tubular trusses of all spans as per approved drawing & design with prefabricated steel applications using quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall cofirm to latest structural welding code. Quality shall be on various parametes like shape, size, design gauge and polish the entire trusses is anchored in RCC column by using 4 nos of M.S anchor bolts at each support with 10 mm thick base plate and shoe plate The work includes cutting, straightening, placing in position of M.S pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift transportation etc., complete and as per the directions of the Engineer-in-charge of the work	Kgs	127.20	655534.10	Rupees One Hundred Twenty Seven and Twenty Paise Only
13	15	Providing precast concrete chairs etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	10000.00	150000.00	Rupees Ten Thousand Only

Assistant Executive Engineer
Byatarayanapura Sub-Division
KRIDL, BEMP, Bangalore

11/7/16

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
14	68.40	Providing and laying flooring using pre polishing water cut/gang saw 19 mm thick Granite slab over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement / colour pigment etc., complete. **using grey granite / Multy Red / Ruby Red / Black / Hassan Green Granite of Width not less than 1200 mm** etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	2697.70	184522.68	Rupees Two Thousand Six Hundred Ninety Seven and Seventy Paise Only
		Total	-		**1559256.97**	

23

Signature of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-Division
KRIDL, BBMP, Bangalore

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

11/7/16